
The Original Ribbon® Rack—IDSA National Design Award Winner PERMANENT DESIGN COLLECTION—MUSEUM OF MODERN ART



Ribbon® Rack Clearances

If mounting the rack parallel to a wall, be sure to leave a minimum of 2-1/2 feet from the wall and 4-1/2 feet on the other side of the rack for bicycles. If mounting the rack perpendicular to a wall, be sure to leave a minimum of 1-1/2 feet from the wall, as the end counts as a space.

Ribbon® Rack Placement Considerations

If racks are to be placed in parallel positions, be sure to allow 12 feet on center of spacing between the racks. This permits 4-1/2 feet clearance for bicycles on each rack, with a 3-foot common area in between for ingress and egress. If racks are to be placed in a series, allow a minimum of 2 feet on center, end to end, to achieve maximum rack capacity. Please note: the racks can be placed 1 foot on center to achieve a "continuous" look, but this will result in a loss of one space, as the end position counts as a space.

Ribbon® Rack Painting Instructions

We recommend using an outdoor spray paint called Krylon. It is available in a wide variety of colors and can be found in just about any hardware store.

Clean surface to be painted with vinegar, removing all dirt and grime. Rinse off, dry thoroughly and apply paint directly to galvanized surface. Using a spray paint will allow the top coat to be seamless with the previous coats. Maintain surface as needed.

A A A RIBBON BIKE RACK CO.

Division of:

BRANDIR INTERNATIONAL, INC. 521 Fifth Avenue, 17th Floor New York NY 10175-1799 USA

Phone: 800-849-3488
Email: info@ribbonrack.com
Web: ribbonrack.com